



- LEGEND**
- CONSTRUCTION LIMITS
- NOTES:**
- CONTRACTOR IS ADVISED THAT EXISTING CHANNEL BANK IS RIPRAPPED AND RIPRAP MAY BE COVERED BY SILT AND/OR VEGETATION.
 - CONTRACTOR SHALL SALVAGE, CLEAN, AND REINSTALL EXISTING RIPRAP (INCIDENTAL). INSTALL NEW NOODOT GRADE RIPRAP AS NEEDED. SEE QUANTITY TABLE ON GENERAL NOTES SHEET FOR ASSUMED RIPRAP QUANTITY. ACTUAL QUANTITY TO BE DETERMINED IN THE FIELD.
 - MANHOLE SHALL BE RAISED USING A PRECAST RISER SECTION. MANHOLE IS ASSUMED TO BE OF BRICK CONSTRUCTION. CONTRACTOR SHALL ASCERTAIN MANHOLE CONDITION PRIOR TO START OF CONSTRUCTION, TO BE PAID AS "RAISE MANHOLE".

THIS DOCUMENT WAS ORIGINALLY ISSUED AND SEALED BY RANDY G. ENGELSTAD REGISTRATION NUMBER PE-6676 ON 5/29/18 AND THE ORIGINAL DOCUMENT IS STORED AT HOUSTON ENGINEERING, INC., 1401 21ST AVE. N, FARGO, ND 58102

No.	Revision	Date	By
2	ADDENDUM 2	5-29-18	BAU
1	ADDENDUM 1	5-23-18	RGE



City of Fargo CITY PROJECT

75.5%

OF MINOT 2018 OUTFALL PIPE REHABILITATION PROJECT AT SWIF ACTION D, PROJECT NO. 3135.2D AT, NORTH DAKOTA

SITE PLAN AREA 9A-9B	SHEET 12 of 81
PROJECT NO. 6027-050	