



1. DETECTABLE WARNING PANELS SHALL BE INSTALLED TO MATCH THE RAMP WIDTH (THE USABLE PORTION OF RAMP).
2. CURB RAMPS SHALL BE CONSTRUCTED IN ACCORDANCE WITH NDDOT STANDARD DRAWING D-750-03.
3. REFER TO NDDOT STANDARD DRAWING D-750-03 FOR ADDITIONAL CURB RAMP TYPES.
4. DESIRABLE TURNING SPACE IS 5' BY 5' OR LARGER WITH A MINIMUM SIZE OF 4' BY 4'. MAXIMUM SLOPE FOR TURNING SPACES IS 2.0% IN ANY DIRECTION.
5. CONCRETE FOR SIDEWALK SECTION IMMEDIATELY BEHIND CURB SHALL BE INSTALLED 6" THICK. THIS APPLIES TO BOTH RAMPS AND TURNING SPACES IMMEDIATELY BEHIND CURB.
6. PROVIDE FLARES AS SPECIFIED IN PLANS. IF NOT SPECIFIED IN PLANS, PROVIDE 1:10 FLARES WHEN ADJACENT TO A CONCRETE PEDESTRIAN CIRCULATION PATH OR 3 FT FLARES WHEN NOT ADJACENT TO A PEDESTRIAN CIRCULATION PATH



SECTION A-A

City Plate No.: STR-8	STANDARD DETAILS PEDESTRIAN CURB RAMP PATHWAY / SIDEWALK	
Last Revision: 12/3/2025		
Section: 3300		