



NOTES:

1. ENCASEMENT MUST BE 8 LF MIN. ALONG THE CARRIER PIPE.
2. WHEN STACKING INSULATION BOARDS, STAGGER EACH LAYER SUCH THAT ALL BUTT JOINTS ARE OVERLAPPED BY THE LAYER ABOVE (18" MIN.)

City Plate No.:	
BED-7	
Last Revision:	
12/18/2020	
Section:	
2100, 2200, 2300, 2400	

**STANDARD DETAILS**  
**ENCASEMENT INSULATION**

**City of Minot**