


**NOTES:**

1. POINT 1 MUST BE A MINIMUM 6" HIGHER THAN POINT 2 TO ENSURE THAT WATER FLOWS THRU THE SILT FENCE AND NOT AROUND THE ENDS.



STEEL FENCE POST (T-POST)  
MINIMUM 5' LONG  
4' MAXIMUM SPACING

POST NOTCHES TO FACE  
AWAY FROM FABRIC

ATTACH FABRIC TO POSTS WITH  
MINIMUM 3 ZIP TIES (50 LB TENSILE) PER  
POST IN TOP 8" OF FABRIC

MONOFILAMENT GEOTEXTILE FABRIC

MACHINE SLICE 8" - 12" DEPTH  
(PLUS 6" FLAP) TRENCH MUST BE  
COMPACTED BY LIGHT EQUIPMENT  
PRIOR TO PLACEMENT OF STEEL POSTS

DIRECTION OF  
SURFACE FLOW

20" MIN. POST EMBEDMENT  
24" FOR SLOPES 3:1 OR GREATER

M:\STANDARD SPECS & DETAILS\2025\Details\ERO-9\_DITCH CHECK\MACHINE SLICED SILT FENCE.dwg

City Plate No.:

ERO-9

Last Revision:

12/18/2020

Section:

1200

**STANDARD DETAILS**

**DITCH CHECK  
MACHINE SLICED SILT FENCE**

**City of Minot**